

SECTION 10000 - MISCELLANEOUS ACCESSORIES

PART 1 - GENERAL

RELATED DOCUMENTS:

Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.

DESCRIPTION OF WORK:

Provide and install the specified products as indicated on the plans and described in the specifications.

NOTE: ALL ITEMS LISTED ARE BY SPECIFIC MODEL NUMBERS BY SPECIFIC MANUFACTURERS; HOWEVER, EQUAL PRODUCTS BY OTHER MANUFACTURER'S OF SIMILAR PRODUCTS WILL BE ACCEPTED UPON APPROVAL (either before or after bidding) BY ARCHITECT. FINAL DECISION OF EQUALITY WILL BE BASED ON ALL QUALITIES AND QUANTITIES OF THE NAMED PRODUCT.

SUBMITTALS:

Product Data: Submit manufacturer's specifications and installation instructions for each of the listed products. Include any operation and maintenance instructions as applicable.

DELIVERY, STORAGE AND HANDLING:

Deliver materials and products in original packages either assembled or "knocked-down" for field assembly.

Store materials inside, under cover and in a manner acceptable to the manufacturer of each product.

PART 2 - PRODUCTS

FIRE EXTINGUISHER CABINETS:

Panorama Model 1037-P42 as manufactured by J.L Industries or approved equal.

Finish and Type: Anodized aluminum, semi-recessed with hall projection limited by handicapped code. Fire extinguishers provided by owner.

Door Type: Frameless white frosted acrylic and black letters reading "FIRE EXTINGUISHER" from the top down on the hinge size.

NOTE: Provide at locations noted on drawings as "FEC".

KNOX BOX:

Furnish and Install one (1) knox box located in the entry of the building. Knox Box shall be sized, purchased and installed in the exterior wall at the direction of the Fire Marshall as manufactured by the Knox Company..

PLAQUE

Furnish and install one (1) dedication plaque located in the entry foyer of the building. Plaque shall be 20" x 30" bronze anodized aluminum with manufacturer's protective finish as manufactured by Andco Industries or equal manufacturer.

Plaque background shall be a leatherette texture contracted by raised "Ribbon" and "Helvetica" lettering.

Edge Condition: Raised Ribbon Edge.

Mounting: concealed type "A".

Erection Date: Provide 4" numerals indicating the year of building completion. "2018"

Number of Letters: 1-1/2" maximum size lettering

"CLEMMONS FIRST BAPTIST CHURCH"

"NARTHEX ADDITION"

3/8" lettering – Text TBD 130 characters. (Scripture or dedication text)

Exact lettering to be supplied by architect 2 months prior to building completion. Plaque supplier to submit shop drawings and full scale rubbing prior to receiving final approval for fabrication.

INTERIOR SIGNAGE:

Furnish and install the following color plastic with acrylic door signs with 1/32" raised lettering and braille copy meeting ADA and ANSI A117.1 requirements.

Type 200A by Mohawk or approved equal.

Sign Sizes: 8" x 8" x 1/8" with 1/2" radiused corners and thin line border around perimeter.

Corners: Radius, 1/2".

Color: To be selected by Architect at a later date.

Installation of Door Signage per manufacturer's standard adhesive method. Locate signs as directed by Architect to meet Handicap Accessibility Code.

Provide the following types and quantities of signage:

1 signs with international symbol for stairs and "STAIR" text with Braille copy.

6 signs with the following on each sign:

1" high room names averaging 15 letters.
Braille copy of text.

TEMPLATE FOR IDENTIFYING RATED WALLS:

Contractor to provide labeling of all rated walls in concealed spaces (in attic and above ceilings) for identification of the required rating and protection at all fire rated openings. Labeling must be permanent but can be sprayed using a template stenciling format or adhered sign.

PART 3: EXECUTION:

INSTALLATION:

Install units in accordance with manufacturer's instructions. Securely anchor to adjacent walls and/or floors with concealed devices as applicable for product specified.

Coordinate with other trades as necessary for proper and timely installation.

ADJUST AND CLEAN:

Ensure that operating parts work freely and fit neatly. Adjust hardware and moving parts as necessary.

Repair or replace damaged parts, dents, buckles, abrasions, or other defect affecting appearance or serviceability.

Clean all products prior to time of final inspection.

END OF SECTION 10000