

14 June 2017

**SUBJECT:** Addendum Number 2  
ROWAN COUNTY AIRPORT  
Terminal Expansion Project  
Salisbury, NC

**FROM:** Ramsay, Burgin, Smith Architects, Inc.  
225 North Main Street, Suite 501  
Salisbury, NC 28144

**Information contained in this Addendum and changes in Drawings and/or Specifications supersede said documents and become part of the Contract. Contractors are reminded to acknowledge receipt of this addendum on their bid Form of Proposal.**

**Architectural Specifications:**

- Item 1- Reference Preformed Metal Roof Panel Systems, Section 07411.  
Regarding reference to Metal Finishes and Custom Color – **eliminate reference to “Custom Color”** and supply manufacturer’s Standard or Premium Blue Color(s). Note that manufacturer must have a “blue” in their range of colors. Base Bid work includes a new Blue Metal Roof System alongside a painted Blue (match new metal) Existing Roof System, Downspouts, etc. Alternate work will include an entirely new Blue Roof System.

**Architectural Drawings:**

- Item 2- Reference Existing/Demo Plan, A2-01. Contractor’s shall assume the existing asphalt paving being demolished (around and under building footprint) is approximately 8 inches thick. Contractors shall patch paving with minimum 4-inch-thick asphalt pavement. (See A4-01)

END OF ADDENDUM No. 2.